

SPECIFICATION GUIDE

MANUFACTURER:

Copperloy, by JH Industries Inc

1981 E. Aurora Road

Twinsburg, Ohio 44087

Phone: (330)-963-4105 (800) 321-4968

Email: Sales@copperloy.com

Fax: (330) 963-4111

www.copperloy.com

Edge of Dock Levelers

Copperloy, by JH Industries, has prepared this guide specification and is intended to assist in preparing a specification for Edge-of-Dock (EOD) levelers, complete with all available options and accessories.

Edit entire section to suit project requirements. Modify or add items as necessary. Delete items which are not applicable. Words and sentences within brackets [____] reflect a choice to be made regarding inclusion or exclusion of a particular item or statement. This section may include performance, proprietary and descriptive type specifications. Edit to avoid conflicting requirements.

This guide specification is written around the Construction Specifications Institute (CSI), Section Format, and standard references to section names and numbers are based on the CSI MasterFormat 2004.

For specification assistance on specific product applications or information about other **Copperloy**, by JH Industries products, please contact our office above.

Copperloy, by JH Industries reserves the right to modify these guide specifications at any time. Updates to this guide may be posted to the manufacturer's website and/or in printed matter as they occur, **Copperloy**, by JH Industries makes no expressed or implied warranties regarding content, errors, or omissions in the information presented.

PART 1 –GENERAL

1.1 SUMMARY

- A. Related Documents: Provisions established within general and supplementary conditions of the contract, Division 1 – General requirements and drawings are collectively applicable to this section.
- B. Related Sections:

1. [Section: 11 13 19.33: Loading Dock Truck Restraints].
2. [Section: 11 13 16: Seals and Shelters].
3. [Section: 11 13 13: Loading Dock Bumpers].

1.2 SYSTEM DESCRIPTION

- A. Design Requirements: Provide fixed-in-place adjustable loading and unloading platform for difference in height and gap between truck bed and building loading dock.
- B. Provide loading dock equipment which has been manufactured, fabricated, and installed to withstand loads specified and to maintain performance criteria stated by manufacturer without defects or failure.
- C. Comply with MH 30.1-2007.

1.3 SUMITTALS

Include submittal requirements below which are consistent with the scope of the project and extent of work of this section. Only request submittals which are necessary for review of design intent.

Do not request submittals if drawings sufficiently describe the products of this section or if proprietary specifying techniques are used. The review of submittals increases the possibility of unintended variations to drawings.

- A. General: Submit in accordance with Section 01 33 00.
- B. Product Data: Submit product data for dock leveler equipment.
- C. Shop Drawings: Submit drawings indicating fabrication and erection of dock levelers including plans, elevations and large-scale details.
 1. Show anchorage, critical installation clearances, connections, and accessory items.
 2. Provide location template drawings for items supported or anchored to permanent construction.
- D. Informational Submittals: Submit following:
 1. Manufacturer's instructions.
- E. Closeout Submittals: Submit following in accordance with Section 07 78 36:
 1. Maintenance data.
 2. Warranty: Specified warranty.

1.4 QUALITY ASSURANCE

- A. Single Source Responsibility: Each component of the edge of dock leveler is required to be from the same manufacturer.
- B. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section with minimum ten years documented experience.
- C. Regulatory Requirements: In compliance with the safety and labeling requirements of ANSI MH30.1-2007.
- D. Certifications: Submit manufacturer's certification that products are furnished for project and meet or exceed specified requirements.

1.5 WARRANTY

- A. Special Warranty: Prepare and submit in accordance with Section 01 78 36.
 1. Manufacturer's standard limited one year warranty for structural components.

PART 2 –PRODUCTS

2.1 MANUFACTURERS

A. Acceptable Manufacturers:

1. **Copperloy**, by JH Industries, 1981 E. Aurora Road, Twinsburg, Ohio, (330)-963-4105, (800)321-4105, www.copperloy.com, email:sales@copperloy.com, Fax: (330) 963-4111

2.2 MECHANICAL EDGE OF DOCK LEVELER

The following description is for a mechanical edge of dock leveler. Select each option and choice according to project need.

A. GENERAL:

1. Capacity: [20,000 lb][30,000 lb] (per ANSI MH 30.1-2007).
2. Platform Width: [66][72][78][84] inches.
3. Platform Deck: [20,000 lb unit] or [30,000 lb unit] safety checker plate steel
4. Lip: [12] inch standard extension beyond bumper, [14] inch on refer models, [20,000 lb units] or [30,000 lb units] safety checker plate steel.
5. Vertical Compensation: Floating travel up and down to compensate for loading and unloading of truck.
6. Service Range: 5 inches above and 5 inches below dock level.
7. Steel bumper blocks with 4 x 10 x 13 inch rubber bumpers on curb embedded channel installations.
8. Rubber: [less rubber bumpers and steel bumper blocks supplied by others]
9. Options:
 - a. [Pit style unit for installation in pit without bumper blocks].
 - b. [Post office style with 2" guard barrier lip].
 - c. [Steel faced bumper guards].

B. Acceptable Product & Manufacturer: **Copperloy**, by JH Industries

Mechanical Edge-of-Dock Leveler Model:

Standard Lip:

[SEL2066CG][SEL2072CG][SEL3066CG][SEL3072CG][SEL3078CG][SEL3084CG].

Refrigerated Lip:

[SEL2066CRG][SEL2072CRG][SEL3066CRG][SEL3072CRG][SEL3078CRG][SEL3084CRG].

2.3 HYDRAULIC EDGE OF DOCK LEVELER

The following description is for a hydraulic edge of dock leveler. Select each option and choice according to project need.

A. General:

1. Capacity: [20,000 lb][30,000 lb] (per ANSI MH30.1-2007).
2. Platform Width: [66][72][78][84] inches.
3. Platform Deck: [for 20,000 lb units] or [for 30,000 lb units] safety checker plate steel

4. Lip: [12] inch standard extension beyond bumper, [14] inch on refer models, [20,000 lb units] or [30,000 lb units] safety checker plate steel.
5. Vertical Compensation: Floating travel up and down to compensate for loading and unloading of truck.
6. Service Range: 5 inches and 5 inches below dock level.
7. Options:
 - a. [Pit style unit for installation in pit without bumper blocks].
 - b. [Post office style with 2 inch guard barrier lip].
 - c. [Steel faced bumper guards].

B. Motor (Hydraulic) Operation:

1. Electrical power pack (includes motor, pump, and valve assembly) of 1 HP, [120][208][240] volt, 60 Hz, [1 phase motor] or [208][240][480][575] volt [3 phase motor].
2. Remote Control Station: Constant pressure push button station complying with NEMA 4.
 - a. Constant pressure on control button: Raise unit.
 - b. Release pressure on button: Allow leveler to descend by gravity to truck bed.
3. Platform operated by hydraulic cylinder.
4. Engineer unit to float with truck bed.

C. Acceptable Model and Manufacturer: **Copperloy**, by JH Industries

Hydraulic Edge of Dock Leveler Model:

Hydraulic Power Packs sold separately.

2.4 FABRICATION

A. Dock Levelers:

1. Weld base frame construction.
2. Unit supplied completely assembled ready for installation.

2.5 FINISHES

A. Dock Levelers:

1. Preparation: Clean surfaces free from slag and splatter, loose mill scale, oil, grease, or rust.
2. Color: Gray.

PART 3 –EXECUTION

3.1 EXAMINATION

- A. Examine conditions and proceed with work in accordance with Section 01 40 00.

3.2 PREPARATION

A. [Pit Mount]

1. Provide dimensions for pit curbing and anchors, rough-in sizes and templates to appropriate trade for installation into recess in accordance with product specifications.
2. Pit embed angle curbing by others.
3. Ensure pit curb angles are level and flush with recess surfaces for pit installations.
4. Ensure that curb angles are in proper place and recess is of adequate size to receive leveler.
5. On Hydraulic powered levelers ensure conduit used to run power have been installed and made ready for installation.

- B. [Face Mount]
 - 1. Provide correct embed channel dimension in accordance with product specifications.
 - 2. Embed channel by others.
 - 3. Ensure channel is properly installed and is flush with the building floor and wall.
 - 4. On Hydraulic powered levelers ensure conduit used to run power have been installed and made ready for installation.
 - 5. Wrap around transition plate.

3.3 INSTALLATION

- A. Dock Leveler: Install in accordance with Section 01 60 00.
 - 1. Install dock levelers [in recesses in loading dock] or to embed channel provided.
 - 2. Level units as required providing flush surface with dock surface; anchor securely flush to substrate.
 - 3. Weld back of leveler frame to [pit curb] to embed channel.
 - 4. Touch-up welds with primer and apply finish to match leveler finish.
 - 5. Connect motor and electrical leads with control units on Hydraulic powered levelers.
 - 6. Remote Control Station: Locate where indicated on Hydraulic powered levelers.

3.4 ADJUSTING AND CLEANING

- A. Adjust installed unit for smooth, safe, efficient and balanced operation.
- B. Remove temporary labels, coverings, and protection of adjacent work areas.
- C. Repair or replace damaged products.
- D. Remove construction debris from site and dispose.

3.5 INSTRUCTION OF OWNER'S PERSONNEL

- A. Instruct Owner's personnel in operation and maintenance of installed units. Provide bound copy of manufacturer's operation and maintenance manual at time of instruction.

END OF SECTION